BRUHAT BANGALORE MAHANAGARA PALIKE

BILL OF QUANTITIES (BOQ)

Name of the work:-Pot hole filling to roads in ward no. 06 (Thanisandra) Byatarayanapura sub division.

Sl. No.	Approved Qty.	Description	Unit	Issued to M/s. Sathya construction	
				In Figures	In Words
1	3357.83	KSRRB M300-2: Making up loss of material / irregularities on shoulder to the design level by adding fresh approved soil and compacting it with appropriate equipment complete as per specifications	Sqm	22.26	Rupees Twenty Two and Twenty Six Paise Only
2	503.67	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material of tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifcations.	Cum	1768.08	Rupees One Thousand Seven Hundred Sixty Eight and Eight Paise Only
3	3357.83	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm.KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, back filling the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2, Complete as per specifications.	Sqm	370.80	Rupees Three Hundred Seventy and Eighty Paise Only

Signature of the Contractor

16/10

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

16/10